

Bid Date: Thursday, February 4, 2021

**City of Grain Valley, Missouri
2021 Pavement Maintenance Program
Asphaltic Concrete Overlay
January 29, 2021
Addendum No. 1**

TO ALL PROSPECTIVE BIDDERS:

Informational:

The public Bid Opening will be held via Zoom Meeting. See the link below to attend.

Join Zoom Meeting

<https://us02web.zoom.us/j/86409355834?pwd=S09ndG1aQkFTY0JnQTErR3NPaENXZz09>

Meeting ID: 864 0935 5834

Passcode: 878164

Dial in number: (312) 626-6799

Pre-Bid Meeting:

A Pre-Bid Meeting was held on January 28, 2021. The Minutes from the meeting are attached.

Bid Opening:

Bid Opening date remains the same Thursday, February 4, 2021 at 2:00 pm

Bid Changes:

The bid form has been revised and Attached to this addendum. The change includes a deductive alternate to use the millings for recycling.

The undersigned hereby acknowledges receipt of this addendum.

PLEASE ATTACH THIS EXECUTED ADDENDUM TO YOUR BID.

Company Name

Signature

Title

Address

City, State, Zip Code

Phone Number

CITY OF GRAIN VALLEY, MO

PRE-BID MINUTES

PROJECT NAME: 2021 PAVEMENT MAINTENANCE PROGRAM

Date: January 28, 2021

Topic: Pre-Bid Meeting - Paving Project

Time: Jan 28, 2021 02:00 PM Central Time (US and Canada)

Join Zoom Meeting

<https://us02web.zoom.us/j/87650765081?pwd=YW5TR0k1Z1ozdTA0Tml5SWUxaVp2QT09>

AGENDA/MINUTES

1. Project: 2021 Pavement Maintenance Program – Asphaltic Concrete Overlay
2. Scope: Cold Milling and Asphalt Overlay
Most of the cold milling will be edge milling 7' wide followed by a 2" overlay of Type 5-01 Asphaltic Concrete. There may be some deep patching, however, the City plans to complete the required patching ahead of the proposed overlay. **Possibility of some deep patching on Dillingham. Eagles Parkway will require full width milling and overlay.**
3. Shop drawings and submittals will consist of Asphaltic Concrete mix design, proposed doorhangers, **schedule** and proposed traffic control plans.
4. Valley Ridge Drive should be scheduled as the last street due to extensive concrete repair needed before the overlay. **At the intersection with Jefferson Road, there is a section of concrete pavement that will require rough surface milling and overlay.**
5. Currently the City plans to issue a Notice to Proceed about May1, 2021 with a completion before June 30, 2021. The delay is to allow the City to complete any required patching and concrete repairs.
6. The bid packet contains a map of the proposed streets as well as a list of streets with the estimated length and width.
7. Questions?
8. **Interest was shown by some bidders to provide a deduct for millings to be used for recycling. Sheet BF-4 has been modified to reflect a deductive alternate for the RAP.**

**ADDENDUM NUMBER 1
REVISED BID SHEET**

ARTICLE 5 - BASIS OF BID

5.01 Bidder will complete the Work in accordance with the Contract Documents for the following price(s):

Project 1-Asphaltic Concrete Overlay

Item No.	Description	Units	Quantity	Unit Price	Extension
1	2-Inch Cold Milling	SY	56,270		
2	4-Inch Cold Milling	SY	12,840		
3	2-Inch Asphaltic Concrete Overlay	Tons	11,350		
4	4-Inch Asphaltic Concrete Overlay	Tons	1,130		
5	Traffic Control	LS	1		
6	Force Account (Set)	1	FA	\$10,000.00	\$10,000.00
Total Amount of Base Bid					

Total Amount of Bid for Project (Typed or Written)

Firm Name

Deduct-

1

Millings Recycled

Tons

TBD



The City reserves the right to adjust quantities for budget purposes